



## PROCEDURES B 727

Preliminary check: flight in shared cockpit:

- Read the Pre Required checklists
- apply the Pre Connection settings relating to the device

Hervé Version 0.5

		PF	PM
<b>Before Start Check List</b>			
Anti Skid	Checked & On	X	
Stall Warning	Checked	X	
Emergency Exit Lights	Armed	X	
Passenger Signs	On		X
Window Heat	Low		X
Anti-Ice	Closed		X
Flight Inst, Altimeters, Flt Directors	Set & X Checked	X	X
Compasses	Sync & X Checked	X	X
Mach Airspeed Warning	Checked	X	
Radios Radar, Transponder	Set & Standby	X	X
Start Levers	Cut Off	X	
Parking Brake	Set On	X	
Rudder Aileron Trim	Checked, Free & Zero	X	
Oxygen & Intephone	Checked, On, 100%	X	X
Fuel	Set For Start		X
Hydraulics	Interconnect Closed, Press & Qty Normal		X
Ground Venturi	Ground Venturi		X
Gear Pins	Sighted & Stowed	X	X
Ships Papers	Complete & Stowed	X	

<b>Cleared For Start / Pushback Check List</b>			
INS	NAV	X	X
Beacon	On	X	
Galley Power	Off		X
Packs	Off		X
A System Pumps	As Required Off For Pushback		X
Start Pressure	xxxxx PSI		X
Ground Equipment	Cleared	X	X
Doors	Closed		X
Cleared For Start Checklist	Complete		X

Cleared After Start / Pushback Check List			
A System Pumps	As Required Off For Pushback		X
Ground Equipment	Cleared	X	X
Doors	Closed		X
After Start Checklist	Complete		X

Before Take Off (Taxi) Check List			
Window Heat	High		X
Anti-Ice	Close / Open		X
Pitot Heat	On & Checked		X
Flight Instruments, FDS & Radios	Set For Departure	X	X
Yaw Damper	On & Checked	X	
Flight Controls	Checked	X	
Speedbrake / Flap Warning	Checked, Detent	X	
Stabiliser Trim	xx Units, Switches Normal	X	
Flaps	Set xx , Green Light	X	
Galley Power	Off		X
Electrical	No Lights, Ess 3		X
Fuel	Set For TO		X
Fuel Heat	Off		X
Hydraulics	Press & Qty Normal		X
Elevator & Rudder Lights	Off		X
Ground Venturi Switch	Normal		X
Air Cond & Press	No2 Bleed Closed Set For TO		X
APU Door	Closed		X
Encoder	Set		X
Cockpit Door	Locked		X
EPR & Airspeed Bugs	Bugs Set	X	X
Take Off Briefing	Completed	X	

Cleared For Takeoff Check List			
Strobes	On	X	
Ignition	Flt Start		X
Transponder	On		X
Landing Lights	On	X	
CSD Oil Cooler	Off		X
Auto Pack Trip Switch	Normal / Cutout		X
Before Takeoff Checklist	Complete		X

After Takeoff Check List			
Ignition	On / Off		X
No Smoking & Seat Belt	Off / On		X
Galley Power	On		X
Anti-Ice	Close / Open		X
Gear	Up & Off		X
Flaps	Up No Lights		X
Auto Pack Trip Switch	Cutout		X
Fuel	Set		X
Hydraulics	Press & Qty Normal		X
Pressurisation	Checked & Set		X
After Take Off Checklist	Complete		X

Decent - Approach Check List			
Seat Belt	On		X
Anti-Ice	Close / Open	X	X
Landing Lights	On		X
Altimeters	Set & X Checked	X	X
Radio Altimeter	Set	X	X
Flight Inst, FDS & Radios	Set & X Checked	X	X
Go Around EPR & V Ref	Bugs Set	X	X
Fuel	Set For Landing		X
Hydraulics	Press & Qty Normal		X
Pressurisation & Cooling Doors	Set		X
Circuit Breakers	Checked		X
Decent - Approach Checklist	Complete		X

Landing Check List			
Anti-Skid	5 Releases		X
Ignition	Flt Start		X
No Smoking	On		X
Gear	Down, In 3 Green	X	
Flaps	xx Green Light	X	
Hydraulics	Press & Qty Normal		X
Landing Checklist	Complete		X

After Landing Check List			
Ignition	Off		X
Window Heat	Off		X
Anti-Ice	Close / Open		X
Pitot Heat	Off		X
Flaps	Up, No Lights		X
Radar Transponder	Stby, Off		X
Speedbrake	Detent		X
Stabiliser Trim	Zero Units		X
Galley Power	Off		X
Fuel	One Pump Per Engine		X
Hydraulics	Interconnect Open, Press & Qty Normal		X
Ground Venturi Switch	Ground Venturi		X
Air Conditioning	Set		X
APU	On Bus		X
After Landing Checklist	Complete		X

Shutdown Check List			
INS	Off	X	X
Seat Belt	Off		X
Beacon	Off		X
Exterior Lights	As Required		X
Start Levers	Cutoff	X	
Parking Brake	Released / Set	X	
Electrical	APU / External Pwr On		X
Fuel	Off		X
Hyd System B Pump Switches	On / Off		X
Air Cond	4 Bleeds Open, Packs Set / Off		X
Oxygen Regulators	Off, 100%	X	X
Shutdown Checklist	Complete		X

Terminating Flight			
Emergency Exit Lights	Off		X
Oxygen Valve	Close		X
Ground Venturi Switch	Normal		X
APU	Off		X
Battery	Off		X
Shutdown Checklist	Complete		X